

Bill of Materials — Project COAST-3 · REV v2

Revision package · Lines 1, 5 changed from v1 · Margin notes attached

PROJECT	REVISION
COAST-3 — Coastal defense wall, Cantabria	v2 (supersedes v1)
ENGINEER	REVIEWED BY
María Soto	Joaquín Núñez · QA
ISSUE DATE	REQUIRED ON SITE
2026-05-04	2026-07-01

LINE	DESCRIPTION	QTY	UOM
1	Hot-rolled structural steel S355J2 , plate, 8 mm thickness (was 6 mm in v1)	80	TON
2	Stainless steel 316L , sheet, 3.0 mm	12	TON
3	Reinforcing bar B500S , diameter 12 mm	22	TON
4	Steel tube S235JR , round, OD 50 mm wall 3 mm	600	M
5	Cold-rolled steel, coil, ~1.2 mm · "premium grade per spec sheet rev. 4" (NEW in v2)	18	TON

📌 MARGIN NOTE LINE 5: OJO — site rep flagged tolerance issue last batch. Hold for QA sign-off before placing PO. If unsure, route to Joaquín. — MS
📌 MARGIN NOTE GENERAL: Asian mill prices spiked +12% — confirm with Han before committing >50 TON on any single line. — MS

DELIVERY & QUALITY

Delivery to **Bay 2, Aceros Ibéricos plant, Bilbao**. Mill certificates required: EN 10204 3.1 for all lines. **Line 5 grade is non-standard** — engineering team has not confirmed exact SAP code.

María Soto
Engineering — Aceros Ibéricos

Joaquín Núñez
QA — Aceros Ibéricos